

Nagpur Metro Project

Double Decker Integrated Road
Cum Metro Corridor


‘Railway span’

05.11.2022



- Nagpur Metro Project Alignment
- Snaps of Works by AFCONS in Reach-03, Reach-01 & Depots
- Brief on Alignment in Reach-02
- Construction Sequence of Double Decker Viaduct
- Snaps of Reach-02 Double Decker Viaduct & Stations
- 80m Railway Span Construction
- Key Highlights & achievements on Railway Span
- Challenges & Solutions during construction of Railway Span


Nagpur Metro Project Alignment



AFCONS executed more than 51% value of Construction works in Nagpur Metro

Works by AFCONS In Reach -03, Reach-01 & Depots

Reach - 03 : Viaduct



Reach - 03 : Sitabuldi Interchange Metro Station



Reach - 01 : Metro Stations

Chattrapati Square Station



J P Nagar Station




Depot works : Hingna & Mihan



Hingna Depot

Mihan Depot



India's longest double decker Metro cum Road Corridor Reach - 02

Located on North South Corridor between Sitabuldi Metro Station to Automotive Metro Station on Nagpur – Jabalpur National Highway (NH-07)

□ Length of alignment : 6.67 km

➤ Length of double decker Viaduct : 5.06 km


➤ Length of Metro Viaduct : 1.61 km

□ Number of Elevated Metro Stations : 6 Nos (4 stations done by AFCONS)

Viaduct : Scope of work


Sr. No.	Activity	Unit	Total Scope
1	Pile	Nos	1687
2	Pile Cap	Nos	221
3	Pier	Nos	386
4	Pier cap	Nos	380
5	Portal Beam (Railway span)	Nos	6
6	Pre-casting units :		7540
6.1	Metro : Segment	Nos	2320
6.2	NHAI : Spine	Nos	1740
6.3	NHAI : Wings	Nos	3480
7	Erection :		
7.1	Metro : Segment	Spans	220
7.2	NHAI : Spine	Spans	168
7.3	NHAI : Wings	Spans	168
8	Railway span (80m) Fabrication & Erection	MT	1650
9	Obligatory span (44m) - 275 MT	Span	1 No.

Typical cross section – Double decker



Construction Sequence of Double Decker Viaduct

Construction Sequence of Double Decker Viaduct



Construction Sequence of Double Decker Viaduct



Construction of Flyover Level Pier



Construction of Flyover Level Pier Cap

Construction of Metro Level Pier & Pier Cap



Metro Level Pier Cap

Flyover Level Pier Cap

Construction Sequence of Double Decker Viaduct



Construction Sequence of Double Decker Viaduct



Wing Launcher for Rib segments erection



Wing launcher for erection of Flyover wing elements

Reach -02

Double decker Viaduct
& Station

-- Photos --



Automotive Ramp –Start of Alignment



Automotive Square



Nari Road Station



Indora Square to Nari Road Station



Indora Square Station to Kadvi Chowk Station



Kadvi Chowk Station



Gaddigodam Station



KCP Station




44m Obligatory Span over Govari Flyover

Finished structure




Asia Book of Records for Double decker on Wardha Road



CERTIFICATE


Maharashtra Metro Rail Corporation Limited and National Highways Authority of India set the record for the Longest Viaduct with Highway Flyover and Metro Rail Supported on Single Column Piers at the Nagpur Metro Rail Project, Maharashtra, India. The National Highway Flyover and Metro Rail System were integrated to form Double Decker viaducts and the section runs for 3.14 km on Wardha Road having three metro stations respectively. The viaduct was opened for Metro Rail traffic on March 05, 2019 and for Highway traffic on November 13, 2020 as confirmed on June 20, 2022.

Date: June 20, 2022


Dr. Biswaroop Roy Chowdhury
Editor-In-Chief
India Book of Records




Le Tran Truong An
Editor-In-Chief
Vietnam Book of Records




Dr. Deepak Chandra Sen
Editor-In-Chief
Nepal Book of Records





Ms. Selvarani Muthiah
President- Malaysia
Asia Book of Records




Dr. Drs. Ponijan Liaw
President
Indonesian Professional
Speakers Association




Gobind Das
Editor-In-Chief
Bangladesh Book of Records



Asia Book of Records is affiliated to World Record University and follows International Protocol of Records (IPRs) as per the consensus arrived at the meeting of the Chief Editors of National Record Books, Ho Chi Minh City, Vietnam.
Asia Book of Records is registered with the Government of India with RNI no HARENG/2011/40693

80m Railway Span Construction

India's Most Iconic Four Layer Multi Transport System



Salient Features of 80m Railway span

Type of Truss	Double Decker Open Web Girder
Span Length	80m
Total Weight of Structure	1650MT
Total no. of HSFG bolts	80,000
Grade of Steel	E – 350 B0
Bearing Type	Spherical Bearings
Nos. of bearings	Total = 06nos.
Height of Truss	12.3m
Truss above from ground level	28m
Erection Methodology	Part Pulling and erection with multiple cranes

Construction sequence & erection method



Site Photos – Four Level multi transport crossing

Gaddigodam

Automotive

At 4th Level
Metro Rail

At 3rd Level
NHA Flyover

At 2nd Level
Indian Railway

At 1st Level
RUB

Completed view of Railway Span

DAY 01/22.12.2021

Erection of 1st member (PART-B) Node -6 LHS



AFCONS

DAY 10/31.12.2021

Erection of Node 6 & 7R , 7-6, 6-5 & 5-4 R BC of (PART-B)




DAY 28/18.01.2022

Erection of 5, 4 TH, 7-4 LHS TC, 5-4 LHS & RHS diagonals, 5-4 BB & FSB of (PART-B)



Construction of 80m Railway span - OWG



Part erection of Steel truss Part 1 (Right of Rail Track), Part – 2 on Left



DAY 44/03.02.2022

Erection of PART – A & **PULLING OF PART – B**

DAY 47/06.02.2022


Erection of PART – A & PART – C

DAY 55/14.02.2022
Erection of PART – A & PART – C

DAY 63/22.02.2022

Complete erection of PART – A & PART – C

Construction of 80m Railway span - OWG



Completion of member erection of Steel Truss

Construction of 80m Railway span - OWG



Deck Slab Construction of Steel Truss

Construction of 2nd level Portal of 80m Railway span - OWG



Prefab cage placing over shutters



Balance reinf. Fixing and side shuttering



Key Features of Portal

- | | |
|------------------------------|----------|
| 1. Reinf. Quantity | = 40T |
| 2. Concrete volume | = 190cum |
| 3. Grade of concrete | = M60 |
| 4. Clear height above ground | = 24m |
| 5. Time duration to complete | = 11days |

Completion of portal

Construction of 80m Railway span - OWG



Test load for NH level = 443.62T
Test load for Metro level = 464.6T
Total test load = **908.22T**

Material used for test load

1. Concrete blocks
2. Sand bags
3. Metro bogie

Span load test at 80m Railway span



80m Railway Span

Key Highlights & achievements during construction of Railway Span

•



- Record Titles approved by Limca Book of Records and **expected to be awarded shortly**
- Record Titles approved by Guinness World Records and **expected to be awarded shortly**

Located at Railway crossing where average train movement is 5 numbers per hour and peak movement is 8 numbers per hour

- Railway span facilitates Four Level multi-transport junction
- Fabrication completed in 80 days (Total 9140 members & 2700 splice plates)
- Trial assembly of entire span completed in 48 days
- Transportation of all the members sequentially done in 96 trailer trips
- Erection done in 3 parts due to area/location constraints. Erection done with 3 erection work fronts and completed in 63 days.
- Pulling of truss across Railway line done in 3.5 hours, distance travelled is 27m. Accuracy of joining Part 2 with Part 1 was within +/- 3 mm.

Key Highlights & achievements of Railway Span

- Total erection done in 436 lifts (Average weight of each lift – 24 T and maximum weight was 42 T)
- 300 number of workforce worked round the clock, 80,000 HSFG bolts fixed with 28 number of torque wrenches
- Dismantling of Temporary Structure completed in 5 days
- Lowering of entire span (4.5m height) done in 2.5 days, 8 number of Single acting hydraulic jacks used for lowering. Lowering done with each layer of 150mm (Lowering rate – 15 minutes per layer)
- Camber was measured upon lowering the span duly resting on four points. Theoretical camber at the centre of span was 83mm and actual value observed was 86mm
- Adjacent spans completed within 19 days after completion of 2nd Level portals of Railway Span

Challenges & Solutions during construction of Railway Span

.

FINALISATION OF METHOD STATEMENT OF ERECTION :

- Presence of Railway hospital, Railway workshop, School, Gurudwara on one side of Railway boundary and on other side residential zone, workshops, garages, shops, curved alignment etc. Narrow road width near Railway boundary.
- Erection of full span on any of the side of Railway track was not possible due to above constraints. Using nose for erection of the span was also examined but was not possible due to space constraint

FINALISATION OF METHOD STATEMENT OF ERECTION :Contd

- To overcome above constraints, method of erection of entire span in 3 parts over temporary support system was explored and finalised.
- Part-2 structure erected on other side of railway track to pull across the tracks to match with erected part – 1 structure followed by erection of balance part - 3 structure.
- **The method was deliberated at various levels at AFCONS, GC, Maha metro, Railways, CRS and advisory technical experts and frozen.**
- **Design of all temporary structures were reviewed and approved by DDC and 3rd party of Mahametro, Railways and CRS including construction stage**

TEMPORARY FOOTING & STRUCTURE OVER RAILWAY EMBANKMENT:

- Temporary footings & supports were required to rest over Railway embankment to reduce the weight of temporary track beams due to radius & space constraint. The span of temporary structure was 25m
- Joint discussions with Railway officials for finalisation of method with full support & active involvement of Maha Metro, Railways gave permission to rest foundations over embankment with strengthening of embankment toes, additional temporary supports for retaining walls of RUB
- Plate load tests were conducted at all 14 temp foundation locations to ensure SBC.
- Method adopted was 1m X 1m X 1m concrete blocks along with structural steel structure retaining walls was adopted to retain embankment slopes.

TEMPORARY FOOTING & STRUCTURE OVER RAILWAY EMBANKMENT:



TEMPORARY FOOTING & STRUCTURE OVER RAILWAY EMBANKMENT :



PULLING OF 'PART – B' OVER RAILWAY TRACKS:

- Entire pulling operation across Railway tracks under one block of four hours, maintaining the alignment to mm accuracy was **most critical**
- Most sophisticated & safe Hillman rollers, each of capacity 350T, (8 numbers) were used for pulling of truss in place of conventional wheel & trolley system.
- Guide rollers & full proof pulling arrangement with synchronised electric winches were deployed including stand by winches/guide rollers.




OBTAINING RAILWAY TRAFFIC BLOCKS:

- The entire construction was completed with minimum of 5 Railway traffic blocks
- Total 4 traffic blocks, each of 1 hour, was taken during erection of temporary track girders across railway line & the removal of the same.
- **One large time traffic block, 4 hours, was taken during pulling operations of truss across Railway line**
- Maha Metro continuously was engaging even with Railway Board for obtaining timely traffic blocks

SAFE LOWERING OPERATION OF ENTIRE TRUSS FOR 4.5MTS:

- Safe Lowering of the assembled truss on to temporary bearings from a height of 4.5m was most critical
- 8nos of 600T hydraulic jacks were used for lowering operation at the initial stage, 2 nos. at each corner bearing points.
- It was lowered in 30 increments of 150mm each and was completed in 2.5 days as against envisaged 6days.
- 1200T hydraulic jacks were used for final lowering after deck slab construction and bearing installation works.

SAFE LOWERING OPERATION OF ENTIRE TRUSS FOR 4.5MTS:



Steel Packing



600T Jack

CREATION OF MULTIPLE ERECTION WORK FRONTS:

- 3 work fronts were created for erection of structural members. 1st from Gurudwara side, 2nd from Itarasi end of Railway line, 3rd from Nagpur end of Railway line
- Approach road of 250m constructed in 5 days time
- Assembly area developed for daily stacking & assembly of elements. Two locations developed for day to day assembly of elements.
- 12 Trailers used to transport fabricated materials from 40 km away fabrication shop. Entire transportation done in the night between 11:00 pm to 06:00 am
- 28 torque wrenches used to cater torquing requirement of average 2200 number of HSFG bolts per day



COLLABORATIVE & SYNCHRONISED WORKING BY STAKEHOLDERS:

- Various Task Force were formed from AFCONS, GC & Maha Metro for various activities and stringent deadlines were given to respective Task Leaders.
- Daily tele conferences were held chaired by MD/Maha Metro without singly break during entire completion period.
- Round the clock monitoring was done by at the Level of Directors of Maha Metro, GC and AFCONS
- Detailed macro level transportation and erection sequence was prepared in advance and monitored continuously.
- Successful Liasoning with all stakeholders such Traffic Police, Railway Authorities, Local Authorities, Gurudwara Committee, Schools etc by Maha Metro & AFCONS was most crucial & critical for smooth execution under most stringent time lines

Thank You...!

